

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21948-00-00
Spot: NWSESW Sec/Twnshp/Rge: 6-6S-20W
990 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: WALLGREN A Well Number: 3
County: ROOKS Total Vertical Depth: 3513 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: RR 1, BOX 28
PHILLIPSBURG, KS 67661

Production Casing Size: 4.5 feet: 3511 w/175 sxs cmt
Surface Casing Size: 8.625 feet: 385 w/250 sxs cmt

#114¹⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/13/2004 1:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: JASON BACH Company: BACH OIL PRODUCTION Phone: (308) 928-2221

Proposed Plugging Method: Ordered out 175 sxs 60/40 pozmix - 10% gel - 14 sxs gel - 500# hulls.
Parted tubing at 3048'.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/13/2004 5:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 4 1/2" - mixed and pumped 25 sxs cement with 200# hulls,
followed with 14 sxs gel and topped with 100 sxs cement with 300# hulls.
Max. P.S.I. 900#. S.I.P. 400#.
Hooked up to the annulus and pumped 25 sxs cement with 100# hulls.
S.I.P. 500#.

RECEIVED
JAN 22 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed Jay Pfeifer (TECHNICIAN)

INVOICED

DATE 1-22-04
INV. NO. 2004061098

JAN 14 2004

PETROLEUM MANAGEMENT, INC.
400 N. WOODLAWN, #201
WICHITA, KS 67208

#3 WALLGREN

6-6-20W
NW SE SW

CONTR RED TIGER DRILLING CO. CTY ROOKS

GEOL _____ FIELD RAY

ELV 2114 KB SPD 2/11/83 CARD ISSUED 3/31/83 IP P 30 BOPD

API 15-163-21,948

SHAW (TOR) 3233-3237
LKC 'A' 3251-3255

+	+
+	+
+	+

LOG	Tops	Depth/Datum
ANH		1605+ 509
B ANH		1635+ 479
OREAD		3161-1047
TOR		3231-1117
LANS		3248-1134
KC		3311-1197
BKC		3442-1328
PRE CAMB		3488-1374
RTD<D		3513-1399

8 5/8 " 385/250SX; 4 1/2 " 3511/175SX

DST (1) 3156-75 (OREAD) / 30-30-30-30, REC 5' OIL STAIN M,
SIP 943-897#, FP 35-35 / 35-35#

DST (2) 3205-3243 (OREAD, TOR) / 45-45-45-45, REC 72' OIL,
62' MO, SIP 908-886#, FP 46-69 / 69-93#

MICT - CO, PF (LKC 'A') 3251-55, AC 1250G, SWB DWN, GSO,
PF (TOR) 3233-37, AC 2500G, SWB LD, GSO, T&R, POP, P 30
BOPD, 3/24/83, COMMINGLED

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

15-163-21,948