

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03430-00-00
Spot: NWSENE Sec/Twnshp/Rge: 11-10S-20W
3630 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: CROFFOOT A Well Number: 6
County: ROOKS Total Vertical Depth: 3787 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 603 MAIN AVE., STE 500
KNOXVILLE, TN 37902

Production Casing Size: 5.5 feet: 3783 100 SX CMT
Surface Casing Size: 8.625 feet: 226 150 SX CMT

123⁰⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/12/2004 8:30 AM
Plug Co. License No.: 30044 Plug Co. Name: LEON'S DRILLING SERVICE
Proposal Rcvd. from: ED GLASSMAN Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered 350 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/12/2004 12:15 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 226' w/150 sxs cement. 5 1/2" casing at 3783' w/100 sxs cement.
Squeezed at 3062' w/150 sxs; 1780' to 1881' w/50 sxs; 1530' to 1600' w/100 sxs cement.
Ran tubing to 3200' - pumped 25 sxs cement with 150# hulls.
Pulled tubing to 2100' - pumped 25 sxs cement with 150# hulls.
Pulled tubing to 1700' - circulated with 80 sxs cement and 200# hulls.
Pulled all tubing - squeezed 5 1/2" casing with 165 sxs cement.
Max. P.S.I. 700#. S.I.P. 300#.
Tied to annulus and pressured to 500#. Took no cement.
Total of 295 sxs 60/40 pozmix - 10% gel and 500# hulls.

RECEIVED
JAN 22 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. ATS-WATER.

Plugged through: TBG

District: 04

Signed Roger A. Moses
(TECHNICIAN)

INVOICE

DATE: 1-22-04
INV. NO. 2004061101

JAN 15 2004

WARRANT


11-10-20W
NW SE NE

I O MILLER #6 CROFFOOT 'A'

Contr. VIRGINIA DRILLING ROOKS County

E. 223¹/₄ RBComm. Comp. 8-9-57 IP 478 BOPD/ARB
PHY POT

Tops	Depth	Datum	Casing
			8" 226
HEEB	3450	-1216	5" 3783
TOR	3476	-1242	DST 3638-70/1 HR, 12' SL OCM 1' OIL, BHP 0#
LANS	3490	-1256	DST 3670-3710/1 HR, 12' MUD, NS, BHP 0#
B/KC	3705	-1471	
CONG	3737	-1503	DST 3783-87/1 HR, 450' OIL, BHP 900#
SIMP	3758	-1524	
SH ARB	3780	-1546	DP: ACID 500: SWB 30 BOPH, NW MARCOTTE POOL 12TH HR
SOL ARB	3782	-1548	
TD	3787	-1553	



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS