

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22454-00-00
Spot: N2N2SW Sec/Twnshp/Rge: 28-8S-24W
2325 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: SCHIERKOLK Well Number: 1
County: GRAHAM Total Vertical Depth: 4415 feet

Operator License No.: 31933
Op Name: M E KLEIN & ASSOCIATES, INC
Address: PO BOX 721436
NORMAN, OK 73070

Production Casing Size: 5.5 feet: 3941 365 SX CMT
Surface Casing Size: 8.625 feet: 232 250 SX CMT

#143.49

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/19/2004 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: CARL ZIMMERMAN Company: M.E. KLEIN & ASSOCIATES, INC. Phone: (785) 635-0692

Proposed
Plugging
Method:

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 01/19/2004 12:00 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

Pumped 300 sxs cement down 5 1/2" casing.
Max. P.S.I. 500#. S.I.P. 150#.
Pressured 8 5/8" to 300#.

RECEIVED
JAN 22 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce D. Basye
(TECHNICIAN)

INVOICED

DATE 1-22-04

INV. NO 2004061100

JAN 20 2004

replacement card

BURCH EXPLORATION
PARKER, CO 80134

28-08 -24W
15'N, C NW NW SW

#1 SCHIERKOLK

site: 1-1/4 S & 2 W OF PENOKEE, KS
contr: WESTERN KANSAS DRILLING
geol: RON MACKEY

city: GRAHAM
field: HOLLEY NORTH

API 15-065-22454

fr date 04/21/88 spd date 05/17/88 drlg comp 05/29/88 card issued 09/21/88 last revised 03/01/89

ELV: 2376 KB LOG	
tops.....	depth/datum
ANH.....	2060 +316
HEEB.....	3652 -1276
LANS.....	3692 -1316
BKC.....	3914 -1538
MARM.....	4022 -1646
MISS.....	4200 -1824
VIOLA.....	4290 -1914
ARB.....	4410 -2034
PBTD.....	3939 -1563
RTD.....	4415 -2039

IP status:
 OIL, P 123 BO & 80 BWPD, LKC 3768-3888 OA,
 CORR & INFO REL: 3/1/89 - ORIG FR IN C N/2 NW NW
 SW; WAS OIL WELL - TIGHT HOLE
 NOTE: CORR: 5/4/88 - ORIG FR AS #2 KEITH
 CSG: 8-5/8" 232 / 250 SX, 5-1/2" 3941 / 365 SX
 NO CORES
 DST (1) 3710-3730 (LKC), / 15-30-45-60, (1ST OP) SB /
 3", (2ND OP) SB / 3", 310' GIP, REC 120' FREE OIL, 186'
 OCMW (25% OIL, 50% W, 15% M, 10% G); 124' OCW
 (15% OIL, 85% W), 1000' W, W / SO THRU-OUT ISIP
 1193# FSIP 1193# IFP 85# -238# FFP 286# -648# IHP
 1921# FHP 1911# BHT 110 °

COPYRIGHT 1989
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

BURCH EXPLORATION
PARKER, CO 80134

28-08 -24W
15'N, C NW NW SW

#1 SCHIERKOLK

DST (2) 3736-3750 (LKC), / TIMES NA, REC 200' M, PKR FAILURE, MISRUN
 DST (3) 3730-3750 (LKC), / 15-30-60-75, (1ST OP) GB / 9.5", (2ND OP) GB / 27", 310' GIP, REC
 80' FREE OIL, 40' MCO (60% OIL, 40% M) ISIP 1040# FSIP 1001# IFP 38# -38# FFP 47# -66#
 IHP 1978# FHP 1969#
 DST (4) 3761-3775 (LKC), / 20-40-80-120, (1ST OP) WB INCR TO FB; (2ND OP) FB / 40", 180'
 GIP, REC 20' FREE OIL, 40' OCM (60% OIL, 40% M), 60' OIL SPTD MW (80% W, 20% M) ISIP
 1155# FSIP 1011# IFP 9# -9# FFP 9# -47# IHP 2007# FHP 1998# BHT 116 °
 DST (5) 3798-3830 (LKC), / 15-30-45-60, (1ST OP) SB / 3", (2ND OP) SB / 3", 120' G IP, REC 15'
 FREE OIL, 145' OCWM (10% OIL, 60% M, 30% W), 240' SLI OCMW (5% OIL, 25% M, 70% W),
 1116' SLI OCW (5% OIL, 98% W) ISIP 1385# FSIP 1375# IFP 152# -343# FFP 343# -706# IHP
 2026# FHP 2017# BHT 112 °
 DST (6) 3879-3891 (LKC), / 15-30-60-75, (1ST OP) SB / 5", (2ND OP) SB / 4", 630' GIP, REC 120'
 FREE OIL, 62' MCO (40% OIL, 20% G, 40% M), 124' OCW (10% OIL, 90% W), 372' OIL SPTD W
 ISIP 1327# FSIP 1289# IFP 47# -66# FFP 114# -276# IHP 2113# FHP 2075# BHT 120 °
 MICT - CO, PF (LANS K) 3880-3882, 3886-3888, W / 4 SPF, AC 1000 GAL (15% NE), GSO, PF
 (LANS E) 3768-3771, W / 4 SPF, AC 1000 GAL (15% NE), GSO, SET 2-7/8" TBG & PKR AT 3792,
 POP, P 123 BO & 80 BWPD, 6/13/88

INVOICE

DATE

BY