

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-21933-00-00
Spot: SWNW Sec/Twnshp/Rge: 3-32S-39W
3300 feet from S Section Line, 660 feet from W Section Line
Lease/Unit Name: MLP GILLESPIE A Well Number: 3
County: STEVENS Total Vertical Depth: 6170 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ
HOUSTON, TX 77227

Production Casing Size: 4.5 feet: 5656 WITH 825 SX CMT
Surface Casing Size: 8.625 feet: 1703 WITH 800 SX CMT

#200⁵³

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/09/2004 1:30 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS & 20 SX CMT. PUMP 40 SX CMT AT 1750'. PUMP 63 SX CMT TO SURFACE AT 600'.
CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/09/2004 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 5656'. PERFS AT 5490-96'. DV TOOL @ 3020' WITH 650 SX CMT. PUMP 200# HULLS & 20 SX CMT DOWN 4 1/2". FOLLOW BOTTOM PLUG WITH 55 BBLs MUD TO 1750'. CHECK WITH WIRELINE. PUMP 20 SX CMT INSIDE 4 1/2" CASING. PUMP 16 BBLs MUD TO 600'. CHECK WITH WIRELINE. PUMP 63 SX CMT TO SURFACE INSIDE 4 1/2" CASING. PRESSURE TO 600 PSIG & SHUT IN. PUMP 5 SX CMT DOWN BACKSIDE. PRESSURE TO 400 PSIG & SHUT IN.

RECEIVED
JAN 21 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Jim Holland
(TECHNICIAN)

INVOICED
DATE 1-21-04
INV. NO. 2004061089

Form CP-17