

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20287-00-01
Spot: NENE Sec/Twnshp/Rge: 3-29S-34W
4620 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: MOODY C Well Number: 3
County: HASKELL Total Vertical Depth: 5500 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ
HOUSTON, TX 77227

Conductor Pipe Size: 20 feet: 30 WITH 3 YDS CMT
Production Casing Size: 5.5 feet: 5499 WITH 375 SX CMT
Surface Casing Size: 8.625 feet: 1772 WITH 775 SX CMT
8178⁷⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/19/2004 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. PLUG AT 1800' WITH 50 SX CMT. PLUG AT 600' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: NONE
Date/Time Plugging Completed: 01/19/2004 5:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:


PBTD 5400'. PERFS AT 5221-41' & 4175-84'. CIBP @ 4390'. PUMP 300# HULLS & 25 SX CMT. 1ST PLUG AT 1800' WITH MUD SPACER & 50 SX CMT. 2ND PLUG AT 600' WITH 30 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
JAN 23 2004
KCC WICHITA

Remarks: USED COMMON CEMENY BY SARGENTS. RECOVERED 1916' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Kevin D. Strube

(TECHNICIAN)

INVOICED

DATE

1-23-04

INV. NO.

2004061106

Form CB 175
[Signature]