

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-21227-00-00
Spot: SWNE Sec/Twnshp/Rge: 26-30S-35W
3300 feet from S Section Line, 1780 feet from E Section Line
Lease/Unit Name: MLP SCOTT A Well Number: 5
County: GRANT Total Vertical Depth: 5600 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ
HOUSTON, TX 77227

Conductor Pipe Size: 20 feet: 75 UNKNOWN
Production Casing Size: 5.5 feet: 5599 WITH 945 SX CMT
Surface Casing Size: 8.625 feet: 1661 WITH 675 SX CMT
#182⁰⁰

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/14/2004 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. PUMP 25 SX CMT AT 1700'. PUMP 60 SX CMT TO SURFACE. PUMP 12 SX CMT DOWN BACKSIDE. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/14/2004 3:45 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:


PBTD 5534'. PERFS AT 5253-66'. DV TOOL @ 2930' WITH 425 SX CMT. CMT AT SURFACE. PUMPED DOWN 5 1/2" 300# HULLS & 25 SX CMT. PUMPED 80 BBLs MUD. PUMPED 25 SX CMT AT 1700'. PUMPED 20 BBLs MUD. PUMPED 60 SX CMT FROM 500' TO 0'. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 500#. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 12 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 500#.

RECEIVED
JAN 23 2004
KCC WICHITA

Remarks: USED COMMON CEMENY BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Kevin D. Strube

(TECHNICIAN)

INVOICED

DATE

1-23-04

WV. NO.

2004061106

FORM 229/3
[Signature]