

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-21216-00-00
Spot: SWNE Sec/Twnshp/Rge: 23-30S-35W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: MLP SCOTT A Well Number: 4
County: GRANT Total Vertical Depth: 5750 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ
HOUSTON, TX 77227

Conductor Pipe Size: 20 feet: 71 UNKNOWN
Production Casing Size: 5.5 feet: 5749 WITH 830 SX CMT
Surface Casing Size: 8.625 feet: 1644 WITH 650 SX CMT
A 186 88

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/14/2004 9:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. PLUG AT 1700' WITH 25 SX CMT. 60 SX CMT TO SURFACE. 10 SX CMT FOR BACKSIDE. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/14/2004 11:30 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:


PBTD 5668'. PERFS AT 5440-44 & 5450-58'. DV TOOL @ 2922' WITH 400 SX CMT. PUMPED DOWN 5 1/2" 300# HULLS & 25 SX CMT. PUMPED 85 BBLs MUD. PUMPED 25 SX CMT TO 1700'. PUMPED 20 BBLs MUD. PUMPED 60 SX CMT FROM 500' TO 0'. MAXIMUM PRESSURE 1500#. SHUT IN PRESSURE 1500#. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 10 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 500#.

RECEIVED
JAN 23 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED

Plugged through: CSG

District: 01



Signed

Kevin D. Strube

(TECHNICIAN)

INVOICED
DATE 1-23-04
INV. NO. 2004061106

Form CB/3
[Signature]