

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-21513-00-01  
Spot: NE Sec/Twnshp/Rge: 30-31S-38W  
3960 feet from S Section Line, 1320 feet from E Section Line  
Lease/Unit Name: MLP SMITH A Well Number: 1  
County: STEVENS Total Vertical Depth: 6158 feet

Operator License No.: 5447  
Op Name: OXY USA, INC.  
Address: PO BOX 27570 5 E GREENWAY PLZ  
HOUSTON, TX 77227

Production Casing Size: 5.5 feet: 6158 WITH 1295 SX CMT  
Surface Casing Size: 8.625 feet: 1671 WITH 1450 SX CMT

# 206<sup>14</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/12/2003 1:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. DISPLACE WITH MUD. PLUG AT 1080' WITH 30 SX CMT. PLUG AT 600' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/13/2004 10:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PERFS AT 4974-78' CIBP @ 5680' PERFS AT 5704-20'. DV TOOL @ 3020' WITH 630 SX CMT. TOC @1255'. PUMP 300# HULLS WITH 25 SX CMT. DISPLACE TO BOTTOM WITH 113 BBL MUD. PRESSURE TO 1000 PSIG & SHUT IN. 1ST PLUG CIRCULATE HOLE WITH MUD & PUMP 30 SX CMT AT 1080'. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 600'. CIRCULATE HOLE & PUMP 30 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. SDON. 01/13/04: LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED  
JAN 21 2004  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1080' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland  
(TECHNICIAN)

INVOICED  
DATE 1-21-04  
INV. NO. 2004061089

Form CP-243