

RECEIVED

JAN 22 2004

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

KCC WICHITA

Form CP-4 December 2003

Type or Print on this Form Form must be Signed All blanks must be Filled

15-163-01689-00-00

Lease Operator: CORSAIR ENERGY, LC

Address: 914 E DOUGLAS AVE

Phone: (316) 267-7779 Operator License #: 5058

Type of Well: OIL Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 10/02/03 (Date)

by: HERB DEINES (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

ARBUCKLE Depth to Top: 3614 Bottom: 3626 T.D. 3640

API Number: 15- 94211953

Lease Name: BAUMGARTNER

Well Number: 4

Spot Location (QQQQ): SW - NE - NE -

4290 Feet from North / South Section Line

990 Feet from East / West Section Line

Sec. 25 Twp. 9 S. R. 19 East West

County: ROOKS

Date Well Completed: 9/20/1953

Plugging Commenced: 10/06/2003

Plugging Completed: 10/06/2003

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out)

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

PERFORATE CASING @ 1975', 1540' & 975'. TIH W/ TBG TO 3582' 40 SXS CEMENT W/ 300# HULLS. POH TO 3260' PUMPED 18 SXS GEL. POH TO 1617' CIRCULATED CEMENT W/ 160 SXS & 300# HULLS. POOH TOPPED OUT WITH 40 SXS CEMENT. PUMPED 75 SXS IN ANNULUS, MAX PSI 100#, SIP 1003. PLUGGING COMPLETE. ALLIED CEMENTERS (60/40, 10% GEL) 11:30 AM, 10/6/03. KCC AGENT: JAY PFEIFER.

Name of Plugging Contractor: PLAINS, INC. License #: 4072

Address: BOX 346, NESS CITY, KS 67560

Name of Party Responsible for Plugging Fees: CORSAIR ENERGY, LC

State of KANSAS County, SEDGWICK, ss.

JAMES G. COLLINS (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) [Handwritten Signature]


(Address) 914 E DOUGLAS, WICHITA, KS 67202

SUBSCRIBED and SWORN TO before me this 21ST day of OCTOBER, 20 03

Notary Public My Commission Expires: August 25, 2004

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202





RECEIVED  
JAN 22 2004  
KCC WICHITA

January 21, 2004

KCC  
Conservation Division  
130 S. Market, Rm 2078  
Wichita, KS 67202

Re Baumgartner #4  
SW/4 Sec. 25-9S-19W  
Rooks County, KS

Dear KCC,

In reviewing the Baumgartner lease file today I came across this original and a copy of the CP-4 form on the #4 well we plugged in October. I expect that it was filed in error and not sent to you.

If you have received a copy please excuse the duplicate.

Please call if you have any questions.

Sincerely,  
Corsair Energy, LLC

  
Jim Collins  
Managing Member

914 East Douglas  
Wichita, Kansas 67202  
(316) 267-7779 P  
(316) 267-4856 F  
[www.corsairenergy.com](http://www.corsairenergy.com)