

15077-21449-00-00
KS-007-21449

WELL PLUGGING RECORD
K.A.R.-82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 207
WICHITA, KS 67202

RECEIVED

JAN 21 2004

KCC WICHITA

API NUMBER _____
LEASE NAME Berthof
WELL NUMBER #3A
660 ft. from ~~S~~^N Section Line
1980 ft. from E Section Line
SEC. 24 TWP. 31 RGE. 9 (E) or (W)
COUNTY Harper
Date Well Completed 2-27-03
12/01/03
Plugging Commenced 12/30/03
Plugging Completed 12/01/03

TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days.

LEASE OPERATOR R & B Oil & Gas, Inc.
ADDRESS Box 195, Attica, KS 67009-0195
PHONE # (620) 254-4251 OPERATORS LICENSE NO. 31191
Character of well ~~oil~~ Gas

(Oil, Gas, D&A, SWD, input, Water Supply Well)

The plugging proposal was approved on 11/30/03 12-2-03 (date)
by Dough Louis (XCC District Agent's Name)

Is ACO-1 filed? yes if not, Is well log attached? _____
Producing Formation Red Eagle Depth to Top 2086 Bottom 2090 T.D. 2925

Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put in	Pulled out
Red Eagle	Gas	2086	2090	8 5/8	224	none
				4 1/2	2190	1830


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set

Sand at 2019, bail 4 sacks cement. Rip pipe at 1830, work free. Pull to 1450, pump 35 sacks cement. Pull to 950, pump 35 sacks cement. Pull to 275, circulate cement to surface with 130 sacks. Pull rest of pipe.

Name of Plugging Contractor Quality Well Sercie, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R & B Oil & Gas, Inc.
STATE OF Kansas COUNTY OF Harper, ss.

Randy Newberry (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.



(Signature) Randy Newberry
(Address) PO Box 195, Attica, KS 67009

SUBSCRIBED AND SWORN TO before me 19th day of January, 2004

Rebecca S. Newberry Notary Public

My commission Expires: 7-21-2005