

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-175-21411-00-00

LEASE NAME Graham

WELL NUMBER 2-3

1503 Ft. from S Section Line

1403 Ft. from E Section Line

SEC. 3 TWP. 32S RGE. 33W (E) or (W)

COUNTY Seward

Date Well Completed 09/27/94

Plugging Commenced 01/15/04

Plugging Completed 01/15/04

RECEIVED

JAN 23 2004

KCC WICHITA

LEASE OPERATOR Chesapeake Operating, Inc.

ADDRESS P. O. Box 18496, Oklahoma City, OK 73154-0496

PHONE# (405) 848-8000 OPERATORS LICENSE NO. 32334

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 06/27/03 (date)

by David Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Morrow Chester Depth to Top 5551 Bottom 5556 T.O. 5843

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Sand Prod</u>			<u>1771</u>	<u>8-5/8</u>	<u>1771</u>	<u>0</u>
			<u>5706</u>	<u>4-1/2</u>	<u>5706</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. MIRU Allied Cmt. Co., pump down 4-1/2" csg w/250# hulls, follow w/20 sx cmt & 50# hulls, plug down followed w/70 bbls mud to displacement, max PSI 1000#, MIRU Log-Tech, perf @1780', pump 430 sx cmt, circ to surface, max PSI 600#, ST, RDMO Allied & Log-Tech, used 450 sx 60/40 6% gel & 300# hulls, final P&A Report

Name of Plugging Contractor Allied Cementing Co., Inc. License No. 99996

Address P. O. Box 31, Russell, KS 67665 (785)483-2626

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chesapeake Operating, Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Jim Reisch (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature] Jim Reisch

(Address) P.O. Box 18496, Okla. City, OK 73154-0496

SUBSCRIBED AND SWORN TO before me this 21st day of January, 2004

My Commission Expires: April 17, 2007 Notary Public



Form CP-4 Revised 05-88

Jan-23-04 10:47A

P.02

ALLIED CEMENTING CO., INC. 13782

Federal Tax I.D.#

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
OAKLEY

DATE <u>1-14-04</u>	SEC <u>3</u>	TWP <u>32S</u>	RANGE <u>33W</u>	CALLED OUT	ON LOCATION <u>9:30AM</u>	JOB START <u>9:45AM</u>	JOB FINISH <u>11:30AM</u>
LEASER <u>GRAHAM</u>	WELL# <u>2-3</u>	LOCATION <u>Sublet to 75-2W-54S-E into</u>			COUNTY <u>SEWARD</u>	STATE <u>Ks</u>	

OLD OR NEW (Circle one)

CONTRACTOR NONE OWNER SAME
 TYPE OF JOB OLD Hole
 HOLE SIZE _____ T.D. _____
 CASING SIZE 4 1/2" DEPTH _____
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

EQUIPMENT

PUMP TRUCK CEMENTER TERRY
 # 300 HELPER MAX WAYNE
 BULK TRUCK # 361 DRIVER LOANER JIM
 BULK TRUCK # _____ DRIVER _____

CEMENT AMOUNT ORDERED 450SKS 604026261
300# HULLS
 COMMON 270SKS @ 8.35 2254.50
 POZMIX 180SKS @ 3.80 684.00
 OEL 23SKS @ 10.4 239.20
 CILORIDE @ _____
 @ _____
 @ _____
 @ _____
 @ _____
 HANDLING 450SKS @ 1.15 517.50
 MILEAGE 0.59 PER SK / MILE 675.00
 TOTAL 4415.00

REMARKS:

Hook on to 4 1/2" casing max 250# HULLS
200SKS cement with 450# HULLS + DISPLACE TO
100' and MAX PRESSURE 1000 PSI PER F.
AT 1780' MAX 430 SKS CEMENT. HAD
CIRCULATION. DID NOT CIRCULATE CEMENT!

THANK YOU

CHARGE TO: CHESAPEAKE OPERATIONS.
 STREET _____
 CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE: Dennis Frick

SERVICE

DEPTH OF JOB _____
 PUMP TRUCK CHARGE 475.00
 EXTRA FOOTAGE @ _____
 MILEAGE 30 MI @ 3.50 105.00
 PLUG @ _____
 @ _____
 @ _____
 TOTAL 580.00

FLOAT EQUIPMENT

_____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____

TOTAL _____

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

Dennis Frick
 PRINTED NAME

CONSERVATION DIVISION
WICHITA, KS

JAN 23 2004

RECEIVED
KANSAS CORPORATION COMMISSION