

To:	STATE CORPORATION COMMISSION	API NUMBER SWSESW 19328 NWSESW 15-121-90,518-00-00
Wichita State Office Bldg. - PLUGGING SECTION	Sec/Twp/Rge 22-17S-22E	
130 S. Market, Room 2078	1346 feet from south section line	
Wichita, Kansas 67202	3535 feet from east section line	
TECHNICIAN'S PLUGGING REPORT	Lease/Well# (GPS CHA 20) MAP 17 Chapman I-7	
Operator License # 101	County MIAMI	
Operator: ST. OF KS. KCC FeeFund	Well Total Depth 335 EST. feet	
Name & FEE FUND	Production Pipe: 2 Size Feet 335	
Address	Surface Casing: 8 7/8 Size Feet 20 EST.	
AB oil well	SWD Well/ Input Well E 03132.54 D & A	
Other well as hereinafter indicated:		
Plugging Contractor: KEPLEY WELL SERVICE	Lic. # 30670	
Address: 19245 FORD ROAD CHANUTE, KS. 66720		
Company to plug at:	Hour: Day: 5 Month: JAN	2004
Plugging proposal received from: MIKE KEPLEY		
Company Name:	KEPLEY WELL SERVICE	Phone: 620-431-9212
Were: PLUG WELL WITH PORTLAND CEMENT FROM TD TO SURFACE.		
Plugging Proposal Received by: FRANK GUILFOYLE		
Plugging attended by Agent:	All <input checked="" type="checkbox"/> Part	None
Operations Completed:	Hour: Day: 8 Month: JAN	2004
Actual Plugging Report:	TRY TO PULL 1" AND PACKER OUT. PULL 1" APART, RUN FISHING TOOL AND PULL TOOL APART. RUN LEFT-HAND PIPE AND HOOK INTO 1". PULL 1" AND PACKER OUT. RUN 3/4" INSIDE 2" TO 320 FT. RUN 1" OUTSIDE 2" TO 125 FT. WASH 1" TO 295 FT. WASH 3/4" TO 335 FT. PUMP PORTLAND CEMENT TO SURFACE INSIDE AND OUTSIDE TO SURFACE. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 65 SACKS OF CEMENT. WELL PLUGGED.	
Remarks: CONTROL NUMBER 20030073 - 016 (If additional description is necessary, use BACK of this form.)		

I DID observe this plugging.

RECEIVED

JAN 26 2004

KCC WICHITA

Signed:  FRANK GUILFOYLE
TECHNICIAN