

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21399-00-00  
Spot: SENW Sec/Twnshp/Rge: 15-34S-8W  
3300 feet from S Section Line, 3300 feet from E Section Line  
Lease/Unit Name: WURM A Well Number: 1-15  
County: HARPER Total Vertical Depth: 4720 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 453 S. WEBB RD. STE 310 PO BOX 7802  
WICHITA, KS 67278

Production Casing Size: 4.5 feet: 4706 140 SX CMT  
Surface Casing Size: 8.625 feet: 267 180 SX CMT 40  
#153

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/15/2004 6:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 532-3292

Proposed Plugging Method: Sand to 4650' and 4 sacks of cement; 1350' and 35 sacks of cement; 900' and 35 sacks of cement; 310' -0' and circulate to surface.

RECEIVED  
KCC DISTRICT #2  
JAN 21 2004

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE WICHITA, KS  
Date/Time Plugging Completed: 01/15/2004 6:00 PM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

The perforations were covered with sand to 4720' to 4650' and capped with 4 sacks of cement. The 4-1/2" casing was recovered from 3420' and pulled to 1350' and 35 sacks of cement was spotted. The casing was pulled to 900' and 35 sacks of cement was spotted. The casing was pulled to 310' and cement was circulated to surface.

60/40 poz mix with 4% gel.


RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 27 2004  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENT TICKET #14642

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

  
(TECHNICIAN)

INVOICED  
DATE 1-27-04  
INVOICE # 2004061113