

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20555-00-00
Spot: N2N2NW Sec/Twnshp/Rge: 19-31S-6W
4950 feet from S Section Line, 3960 feet from E Section Line
Lease/Unit Name: HOSTETLER Well Number: 2
County: HARPER Total Vertical Depth: 4840 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 453 S. WEBB RD. STE 310 PO BOX 7802
WICHITA, KS 67278

Production Casing Size: 5.5 feet: 4837 260 SX CMT
Surface Casing Size: 8.625 feet: 318 230 SX CMT

#157³⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/14/2004 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 532-3292

Proposed Plugging Method: Sand to 4571' and 5 sacks of cement; 1300' and 35 sacks of cement; 700' and 35 sacks of cement; 350' - 0' and circulate to surface. Recovered 3220' 5-1/2" casing. Perforations @ 4631'-4663'.

RECEIVED
KCC DISTRICT #2

~~JAN 21 2004~~

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 01/14/2004 1:00 PM KCC Agent: STEVE VANGIESON WICHITA, KS

Actual Plugging Report:

The perforations were covered with sand to 4571' and capped with 5 sacks of cement. The 5-1/2" casing was recovered from 3200' and pulled to 1300' and 35 sacks of cement was spotted. The casing was pulled to 700' and 35 sacks of cement was spotted. The casing was pulled to 350' and cement was circulated to surface.

60/40 poz mix with 4% gel.

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 27 2004

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENT TICKET #14590

Plugged through: CSG

District: 02

Signed _____

[Signature]
INVOICE (TECHNICIAN)

DATE 1-27-04
INV. NO. 2004061113