

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21468-00-00  
Spot: NENENWNE Sec/Twnshp/Rge: 29-31S-7W  
165 feet from N Section Line, 1435 feet from E Section Line  
Lease/Unit Name: MATHES Well Number: 1-A  
County: HARPER Total Vertical Depth: 2240 feet

Operator License No.: 31093  
Op Name: BECKER OIL CORPORATION  
Address: 122 E. GRAND, STE. 212  
PONCA CITY, OK 74601

Surface Casing Size: 8.625 feet: 239 200sx Cement  
72<sup>80</sup>

Well Type: GAS DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/30/2003 12:00 AM  
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY  
Proposal Rcvd. from: GARY TALBOT Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 35 sacks @ 1500'; 35 sacks @ 1000'; 50 sacks @ 290'; 25 sacks @ 60'; and 15 sacks in rathole.

RECEIVED  
KCC DISTRICT #2  
DEC 31 2003

WICHITA, KS

Plugging Proposal Received By: DOUG LOUIS  
Date/Time Plugging Completed: 12/30/2003 7:00 AM

Witness Type: Plugging Operations Were Not Witnessed  
KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

The drill pipe was ran open-ended to 1500' where 35 sacks of cement was spotted. The drill pipe was pulled to 1000' where 35 sacks of cement was spotted. The drill pipe was pulled to 290' where 50 sacks of cement was spotted. The drill pipe was pulled to 60' where cement was circulated to surface.

The rathole was circulated with 15 sacks of cement.

60/40 poz mix with 4% gel.


RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 27 2004  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING

Plugged through: DP

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

**INVOICED**

DATE 1-27-04

INV. NO. 2004061111