

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-017-20121-00-00
Spot: NWSENW Sec/Twnshp/Rge: 2-20S-7E
1650 feet from N Section Line, 1650 feet from W Section Line
Lease/Unit Name: STAUFFER Well Number: 1
County: CHASE Total Vertical Depth: 1977 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 1400 UNKNOWN
Surface Casing Size: 7 feet: 150 UNKNOWN

#6425

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL DBA MCPHERSON DRILLING CO.
Proposal Rcvd. from: LAWRENCE JACKSON Company: AMERICAN ENERGIES CORP. Phone: (620) 793-6214

Proposed
Plugging
Method:

CEMENT PLUG @ PERFORATION, FILL CASING WITH MUD. PLACE 20 SX PLUG ON TOP OF 4 1/2" CASING.
RECEIVED
KCC DISTRICT #2
JAN 23 2004

Plugging Proposal Received By: MICHAEL WILSON
Date/Time Plugging Completed: 12/22/2003 5:00 PM

Witness Type: COMPLETE (100%)
KCC Agent: MICHAEL WILSON

WICHITA, KS

Actual Plugging Report:

Ran tubing to 1,259' and spotted 42 sxs. cement. Pulled tubing to 250' and circulated 56 sxs. cement to the surface. Ran tubing on the outside of 4 1/2" casing to 35' and circulated 12 sxs. cement to the surface.

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 27 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY UNITED CEMENTING & ACID CO., INC. INVOICE #5070.

Plugged through: TBG

District: 02

Signed Michael R Wilson
(TECHNICIAN)

INVOICED
DATE 1-27-04
INV. NO 2004061110