

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-017-20122-00-00  
Spot: SENYSE Sec/Twnshp/Rge: 35-19S-7E  
1650 feet from S Section Line, 1650 feet from E Section Line  
Lease/Unit Name: STAUFFER Well Number: 2  
County: CHASE Total Vertical Depth: 1842 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N. MARKET, STE 710  
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 1385 UNKNOWN  
Surface Casing Size: 7 feet: 150 UNKNOWN  
87  
\$ 59

Well Type: Gas UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/19/2003 1:00 PM  
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL DBA MCPHERSON DRILLING CO.  
Proposal Rcvd. from: LAWRENCE JACKSON Company: AMERICAN ENERGIES CORP. Phone: (620) 793-2146

Proposed Plugging Method: SET CEMENT PLUG ON PERFORATION @ 753-37, FILL WITH MUD, 20 SX PLUG ON TOP OF THE 4 1/2" CASING.

RECEIVED  
KCC DISTRICT #2

JAN 23 2004

Plugging Proposal Received By: MICHAEL WILSON Witness Type: COMPLETE (100%) WICHITA, KS  
Date/Time Plugging Completed: 12/19/2003 5:30 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

C.I.B.P. sat at 800'. Ran tubing to 753' and circulated 116 sxs. cement to the surface. Ran tubing on the outside of 4 1/2" casing to 65' and circulated 15 sxs. cement to the surface.

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 27 2004

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY UNITED ACID & CEMENTING CO., INC. INVOICE #5069.

Plugged through: TBG

District: 02

Signed Michael R Wilson  
(TECHNICIAN)

INVOICED  
DATE 1-27-04  
INV. NO. 2004061110