

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-30086-00-00  
Spot: NWNE Sec/Twnshp/Rge: 35-27S-7W  
4620 feet from S Section Line, 1980 feet from E Section Line  
Lease/Unit Name: MCKENNA Well Number: 1  
County: KINGMAN Total Vertical Depth: 3698 feet

Operator License No.: 31337  
Op Name: WILDCAT OIL & GAS LLC  
Address: 10286 SW 170TH AVE  
NASHVILLE, KS 67112

Production Casing Size: 4.5 feet: 3698 100 SX CMT  
Surface Casing Size: 8.625 feet: 290 250 SX CMT  
\$ 120<sup>19</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/20/2004 1:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MACE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Sand to 3467' and 4 sacks of cement; 1150' and 35 sacks of cement; 650' and 35 sacks of cement; 340' - 0'.

RECEIVED  
KCC DISTRICT #2  
JAN 23 2004

Plugging Proposal Received By: JACK LUTHI Witness Type: COMPLETE (100%) WICHITA, KS  
Date/Time Plugging Completed: 01/20/2004 4:30 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Sanded bottom to 3467' and 4 sacks of common cement. Shot 4-1/2" casing off at 2230'. Pulled to 1750' and pumped 35 sacks of cement. Pulled to 650' and pumped 35 sacks of cement. Pulled to 340' and circulated cement to surface.

60/40 poz mix with 4% gel.

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 02 2004  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED TICKET #14618

Plugged through: CSG

District: 02

Signed Jack L Luthi  
(TECHNICIAN)

INVOICED  
DATE 2-2-04  
INV. NO. 2004061138