

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21122-00-00
Spot: N2S2SE Sec/Twnshp/Rge: 20-17S-7W
990 feet from S Section Line, 1400 feet from E Section Line
Lease/Unit Name: RATHBUN TRUST Well Number: 1-20
County: ELLSWORTH Total Vertical Depth: 3550 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING INC DBA LARS
Address: 562 WEST HIGHWAY 4
OLMITZ, KS 67564

Surface Casing Size: 8.625 feet: 274

#115³⁸

Well Type: DH UIC Docket No: Date/Time to Plug: 01/21/2004 9:30 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: STEVE STEPHENS Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1000' and 35 sacks of cement; 650' and 35 sacks of cement; 325' and 35 sacks of cement; 60' and 25 sacks of cement.
Rathole -- 15 sacks of cement.

RECEIVED
KCC DISTRICT #2
JAN 23 2004

Plugging Proposal Received By: JACK LUTHI WitnessType: NONE WICHITA, KS
Date/Time Plugging Completed: 01/21/2004 11:00 AM KCC Agent: JACK LUTHI

Actual Plugging Report:

Ran drill pipe to 1000' and pumped 35 sacks of cement. Pulled to 650' and pumped 35 sacks of cement. Pulled to 325' and pumped 35 sacks of cement. Pulled to 60' and pumped 25 sacks of cement. Pumped 15 sacks of cement into rathole.

60/40 poz mix with 4% gel.

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 02 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED TICKET #14369

Plugged through: TBG

District: 02

Signed Jack L Luthi
(TECHNICIAN)

INVOICED
DATE 2-2-04
INV. NO. 2004061629