

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-13187-00-00
Spot: SWNENE Sec/Twnshp/Rge: 7-21S-11W
4290 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: SCHLOCHTERMEIER Well Number: 2
County: STAFFORD Total Vertical Depth: 3462 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Production Casing Size: 4.5 feet: 3440
Surface Casing Size: 8.625 feet: 251

#112⁵²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/22/2004 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO Phone: (316) 265-3311

Proposed Plugging Method: RUN TUBING TO 3440' & PUMP 30 SX GEL - 300# HULLS - 25 SX CMT. PULL TUBING AND PUMP 100# HULLS & 25 SX CMT. PERFORATE AND CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/22/2004 1:55 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:


PERFS AT 3232-3236'. OPEN HOLE 3440-3462'. TOC = 3035'. ANHYDRITE @ 500'. RAN TUBING TO 3380' & PUMPED 30 SX GEL - 300# HULLS - 25 SX CMT. PULLED TUBING TO 3200' & PUMPED 100# HULLS & 25 SX CMT. PERFORATED 4 1/2" @ 500'. PULLED TUBING TO 500'. CIRCULATED CMT TO SURFACE UP 4 1/2" & 4 1/2" x 8 5/8" ANNULUS WITH 140 SX CMT. PULLED TUBING OUT OF HOLE. TOPPED OFF HOLE WITH 45 SX CMT.

RECEIVED
JAN 28 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE 1-29-04
2004061119

[Signature]
Form CP-2/3