

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21017-00-01
Spot: SWSNW Sec/Twnshp/Rge: 36-27S-5W
3300 feet from S Section Line, 3480 feet from E Section Line
Lease/Unit Name: DURFEE Well Number: 1
County: KINGMAN Total Vertical Depth: 1914 feet

Operator License No.: 32009
Op Name: SPS, INC.
Address: 734 N. LINCOLN
CHENEY, KS 67025

Production Casing Size: 5.5 feet: 1914 125 SX CMT
Surface Casing Size: 8.625 feet: 218 200 SX CMT

#62²¹

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/22/2004 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MACE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Sand to 1500' and 5 sacks of common cement; 900' and 35 sacks of cement; 550' and 35 sacks of cement; 270' - 0'.

RECEIVED
KCC DISTRICT #2

JAN 23 2004

Plugging Proposal Received By: JACK LUTHI Witness Type: PARTIAL WICHITA, KS
Date/Time Plugging Completed: 01/22/2004 12:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Sanded bottom to 1500' and 5 sacks of common cement. Shot 5-1/2" casing off at 1300'. Pulled to 900' and pumped 35 sacks of cement. Pulled to 550' and pumped 35 sacks of cement. Pulled to 270' and circulated cement to surface.

60/40 poz mix with 4% gel.

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 02 2004

CONSERVATION DIVISION
WICHITA, KS

Remarks: ACID TICKET #7779

Plugged through: CSG

District: 02

Signed Jack Luthi
(TECHNICIAN)

INVOICED

DATE

INV. NO.

2.2.04
2004061136