

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-21333-00-00  
Spot: W2W2SE Sec/Twnshp/Rge: 3-24S-18W  
1320 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: BRITTON TRUST A Well Number: 2  
County: EDWARDS Total Vertical Depth: 4530 feet

Operator License No.: 5118  
Op Name: TGT PETROLEUM CORPORATION  
Address: 7570 W 21ST ST N, STE1010D PO BOX  
WICHITA, KS 67275

Production Casing Size: 5.5 feet: 4529 WITH 250 SX CMT  
Surface Casing Size: 8.625 feet: 416 WITH 250 SX CMT

#147<sup>23</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/14/2004 12:00 PM  
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC  
Proposal Rcvd. from: HAROLD BELLERIVE Company: TGT PETROLEUM Phone: (316) 773-2266

Proposed Plugging Method: CIBP @ 4075' WITH 2 SX CMT. PLUG AT 1200' WITH 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/14/2004 5:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4505'. PERFS AT 4114-15'. SET CIBP @ 3995' & 2 SX CMT WITH BAILER. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 1200' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 445' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED  
JAN 28 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 1500' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
JAN 20 2004  
KCC Dodge City

Signed Richard W. Lacey  
(TECHNICIAN)

INVOICED  
DATE 1-29-04  
INV. NO. 200406121

Forms CP-223