

Corrected report

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-20057-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 33-23S-16E  
3640 feet from S Section Line, 1300 feet from E Section Line  
Lease/Unit Name: FULLER Well Number: 12  
County: WOODSON Total Vertical Depth: 1100 feet

Operator License No.: 32710  
Op Name: LAYMON OIL II, LLC  
Address: 1998 SQUIRREL RD  
NEOSHO FALLS, KS 66758

Production Casing Size: 4.5 feet: 1100  
Surface Casing Size: 7 feet: 40

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/14/2004 10:30 AM  
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC  
Proposal Rcvd. from: KENNETH LAYMON Company: LAYMON OIL II, LLC Phone: (620) 963-2495

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 1100' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE  
Date/Time Plugging Completed: 01/16/2004 1:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE TOP OF THE 4 1/2" CASING PROVED UNSOUND. THE CASING WAS PERFORATED AT 800', AT 600', AND THE 4 1/2" CASING WAS PARTED AT 225' AND 225' OF 4 1/2" WAS REMOVED. 1" PIPE WAS RAN INTO THE WELL TO 100'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE WELL AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. APPROXIMATELY 125 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED RECEIVED  
KCC District #3  
JAN 26 2004  
KCC WICHITA JAN 23 2004  
Chanute, KS

Remarks: A PLUGGING REPORT SUBMITTED 1/15/2004 WAS INCORRECT. THE PLUGGING WAS COMPLETED AS ST

Plugged through:

District: 03 Signed Clayton Titel by BL  
(TECHNICIAN)