

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21833-00-00
Spot: NENWSE Sec/Twnshp/Rge: 29-9S-24W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: HOETING UNIT Well #: 2-10
County: GRAHAM Total Vertical Depth: 4175 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PROD Size: 4.5 feet: 4170 175 SX CMT
SURF Size: 8.62 feet: 249 175 SX CMT

8/35 69

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/21/2004 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 200 sxs Multi-Density Cement and 500# hulls.
DV at 2230' w/350 sxs.
Perfs 4074' - 4076'; 4094' - 4100'.

Plugging Proposal Received By: PAT STAAB Witness Type: PARTIAL
Date/Time Plugging Completed: 01/21/2004 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 2356' - pumped 100 sxs MDC with 500# hulls to circulate cement to surface.
Pulled tubing - tied onto 4 1/2" casing with a swedge and pumped 50 sxs MDC.
Max. P.S.I. 500#. S.I.P. 400#.
Tied onto backside - pumped 5 sxs MDC.
Max. P.S.I. 350#. S.I.P. 350#.

Perfs:	
Top	Bot
4094	4100
4074	4076

RECEIVED
FEB 02 2004
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS GEORGE NICKELSON #10-29. SWIFT SERVICES, INC. - TICKET #6252

Plugged through: TBG

District: 04

Signed *Pat Staab*
(TECHNICIAN)

INVOICED

DATE 2-2-04

INV. NO. 2004061133

JAN 27 2004

DATE

WELL

WADICET

29-9-24W
NE NW SE

DON E. PRATT
P.O. BOX 370

#10-29 GEORGE NICKELSON

HAYS, KS 67601
CONTR MURFIN DRLG. CO.

CTY GRAHAM

GEOLOGICAL

FIELD HOETING

ELV 2557 KB SPD 8/12/83 CARD ISSUED 1/19/84 IP P 15 BO & 40 BWPD
LKC 4094-4100 OA

+	+	+
+	+	+
+	+	+

API 15-065-21,833

SMP	Tops	Depth/Datum
ANH	2217+	340
B/ANH	2258+	299
TOP	3641-	1084
HEEB	3858-	1301
TOR	3880-	1323
LANS	3897-	1340
BKC	4126-	1569
RTD	4175-	1618

8 5/8 " 249/175 SX; 4 1/2 " 4170/525 SX (TWO STAGED); DV
TOOL AT 2240
DST (1) 3887-3965 (TOR, LKC) TIMES NA, FB THRU-OUT, REC
495' GSY WTRY DM, W / SPKS OIL, SIP 748-731#, FP 52-191 /
191-279#
DST (2) 3957-4020 (LKC) / 60-30-60-30, REC 434' LIGHT GSY
CUT WTRY DM, NSO, SIP 644-609#, FP 52-192 / 192-261#
DST (3) 4018-65 (LKC) / 30-30-0-0, WB, DIED 17", FLUSHED
TOOL, NO HELP, SIP 63' DM, ISIP 592#, IFP 34-52#
DST (4) 4060-4105 (LKC) / 60-30-60-30, 186' GIP, REC 372' TF
(62' VHOCM, 124' LIGHT OCM, 186' WTRY DM), SIP 851-834#,
FP 52-174 / 174-244#
MIST - CO, PF (LKC) 1/4095, 1/4075, (LTD ENTRY), AC 500 G
(15% SGA), SWB DWN, SO, PF (LKC) 4094-96 & 4074-76, W/4
SPF, SWB DWN, REC 4 BFP (37% OIL) LAST HR OF 3 HR TEST,
PF (LKC) 4096-4100, W/4 SPF, AC ALL ZNS W/3500 G (15%
GSA), ONFU 1400' FL (50% OIL), SWB 4 HRS, LAST HR REC 13
BF (32% OIL), T & R, POP, P APPX 15 BO & 40 BWPD, 9/16/83

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS