

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20316-00-00
Spot: S2S2SW Sec/Twnshp/Rge: 26-29S-14W
330 feet from S Section Line, 1320 feet from W Section Line
Lease/Unit Name: SHRIVER Well Number: 1
County: PRATT Total Vertical Depth: 4575 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 804, LB 30
DALLAS, TX 75205

Production Casing Size: 4.5 feet: 3941 WITH 75 SX CMT
Surface Casing Size: 10.75 feet: 241 WITH 225 SX CMT
\$148⁶⁹

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/12/2004 12:30 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS Phone: (214) 219-8883

Proposed Plugging Method: PER KCC RULES & REGULATIONS

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/12/2004 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 3890'. PERFS AT 3848-3851'. UNABLE TO GET BACK TO BOTTOM OF HOLE. KEPT GETTING OUTSIDE 4 1/2" CASING @ SHALLOW DEPTHS. 4 1/2" CASING PULLED & REPLACED WITH CASING PATCH AT 510'. AFTER REPAIRS & SQUEEZE AT 510' GOT OUT OF HOLE AGAIN AT APPROXIMATELY 900'. TENSION PACKER HUNG UP & LEFT IN HOLE 60' ABOVE PERFORATIONS. RED BEDS FELL IN ON PACKER. RAN TUBING INTO 907', GOT OUT OF HOLE. PULLED UP TO 893'. PUMPED DOWN 2 3/8" TUBING WITH 175 SX CMT WITH 500# HULLS MIXED IN CMT BEFORE CMT CIRCULATED UP 4 1/2" CASING TO SURFACE. LAID DOWN TUBING. PUMPED DOWN 4 1/2"/10 3/4" ANNULUS WITH 100 SX CMT. MAXIMUM PRESSURE 250#. SHUT IN PRESSURE 125#. TOPPED OFF 4 1/2" CASING WITH 25 SX CMT.

RECEIVED
FEB 02 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01

RECEIVED
JAN 23 2004
KCC Dodge City

Signed Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
DATE 2-2-04
INV. NO. 2004061131

Form 218