

WELL PLUGGING RECORD

K.A.R.-82-3-117

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

RECEIVED

JAN 21 2004

KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out Completely  
and return to coms. div.  
office within 30 days.

API NUMBER 2/11/59  
15-155-19029-00-01  
LEASE NAME Lawson-Jones  
WELL NUMBER A-2  
3630 ft. from S Section Line  
1650 ft. from W Section Line  
SEC. 15 TWP. 26 RGE. 9 (E) or (W)  
COUNTY Reno  
Date Well Completed 1957 10-08-1957  
Plugging Commenced 11/24/03  
Plugging Completed 11/24/03

LEASE OPERATOR R & B Oil & Gas, Inc.  
ADDRESS 111 N. Blaine, Attica, KS 67009  
PHONE # (620) 254-7251 OPERATORS LICENSE NO. 31191

Character of well oil gas  
(Oil, Gas, D&A, SWD, input, Water Supply Well)

The plugging proposal was approved on 11/24/03 10-02-03 (date)  
by Doug Louis (XCC District Agent's Name)

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation Miss Depth to Top NA Bottom N/A T.D. 4100

Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put in	Pulled out
<u>Miss</u>	<u>Gas</u>	<u>N/A</u>	<u>N/A</u>	<u>12 1/2</u>	<u>307</u>	<u>none</u>
				<u>4 1/2</u>	<u>4019</u>	<u>2430</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Sand at 3600, bail 4 sacks cement. Rip pipe at 2511, 2430, work free and pull to 1400. Pump 35 sacks cement. Pull to 800', pump 35 cement. Pull to 380, circulate cement to surface w/230 sacks. Pull rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925  
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R & B Oil & Gas, Inc.  
STATE OF Kansas COUNTY OF Harper, ss.

Randy Newberry (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

**JANE SWINGLE**  
Notary Public - State of Kansas  
My Appt. Exp. 1-6-07

(Signature) Randy Newberry  
(Address) PO Box 195, Attica, KS 67009  
SUBSCRIBED AND SWORN TO before me 20 day of January, 2004

Jane Swingle, Notary Public  
My commission Expires: 1-6-2007