

15-019-19176 0000

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER N/A, DRLD. BEFORE 1960  
NW NE NE Sec/Twp/Rge 2-32-10E  
4950 feet from south section line  
1056 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3591  
Operator: C & E OIL CO.  
Name & ROUTE 1, BOX 1B2  
Address MOLINE, KS 67353

Lease/Well# HENRY JULIAN # 0W-1  
County CHAUTAUQUA  
Well Total Depth 2100 feet  
Production Pipe: 7" Size Feet 2100  
Surface Casing: 12" Size Feet N/A  
SWD Well/ Input Well D & A

AB oil well  Gas Well

Other well as hereinafter indicated:

Plugging Contractor: C& EOIL CO. Lic. # 3591

Address: ROUTE 1, BOX 1B2, MOLINE, KS 67353

Company to plug at: Hour:          Day: 17 Month: 11 2003

Plugging proposal received from: ED TRIBOULET

Company Name: C & E OIL CO. Phone: 316-647-3601

Were: TO PUMP CEMENT FOR BOTTOM, MIDDLE, & TOP PLUGS.

Plugging Proposal Received by: RON ROWE

Plugging attended by Agent: All  Part  TECHNICIAN  
None

Operations Completed: Hour:          Day: 4 Month: 12 2003

Actual Plugging Report: DUMP-BAILED SAND BACK TO PERFS. @ 1660', RAN 2" TUBING TO 1660' & PUMPED 7 SACKS CEMENT FOR BOTTOM PLUG. PULL 2" TO 1000' & PUMPED 4 SACKS CEMENT FOR MIDDLE PLUG. PULL 2" & RIPPED & PULLED 400' OF 7" OUT. RUN 2" BACK IN TO 350' & PUMPED/ CIRCULATED CEMENT TO SURFACE WITH 60 SACKS CEMENT. PULLED 2" & TOPPED-OFF WELL. USED TOTAL OF 71 SACKS CEMENT.

Remarks: (If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED  
JAN 15 2004  
KCC WICHITA

Signed: RON ROWE  
TECHNICIAN

