

15-049-19037.00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3591Operator: C & E OIL CO.Name & ROUTE 1, BOX 1B2Address MOLINE, KS 67353AB oil well X Gas Well SWD Well/ Input Well Other well as hereinafter indicated: Plugging Contractor: C & E OIL CO.Lic. # 3591Address: ROUTE 1, BOX 1B2, MOLINE, KS 67353Company to plug at: Hour: Day: 21 Month: 11 2003Plugging proposal received from: ED TRIBOULETCompany Name: C & E OIL CO.Phone: 316-647-3601Were: TO PUMP CEMENT FOR BOTTOM, MIDDLE, & TOP PLUGS.

Plugging Proposal Received by:

RON ROWEPlugging attended by Agent: All Part TECHNICIAN
X None Operations Completed: Hour: Day: 18 Month: 12 2003Actual Plugging Report: DUMP-BAILED SAND BACK TO 1845'. RAN 2" TUBING IN 7" CASINGTO 1845' & PUMPED 5 SACKS CEMENT FOR BOTTOM PLUG. PULLED 2" TO 1050' & PUMPED 4 SACKSCEMENT FOR MIDDLE PLUG. PULLED 2" OUT. RIPPED 7" & PULLED 240' OF 7" OUT.RAN 2" BACK IN TO 350' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 2" AND TOPPED-
OFF WELL.USED TOTAL OF 80 SACKS CEMENT.Remarks: (If additional description is necessary, use BACK of this form.)I DID observe this plugging.

Signed:

RON ROWE

TECHNICIAN

RECEIVED

JAN 15 2004

KCC WICHITA