

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

RECEIVED  
JAN 26 2004  
KCC WICHITA

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: XTO Energy Inc.  
Address: 210 Park Ave., Suite 2350 Oklahoma City, Oklahoma 73102  
Phone: (405) 319-3208 Operator License #: 32864  
Type of Well: SWD Docket #: D-13132  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: Submitted 11-19-2003 (Date)  
by: Steve Durward (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Glorietta Depth to Top: 1412' Bottom: 1422' T.D. 1507'  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 081-30097-00-00  
Lease Name: Nilson SWD  
Well Number: 2D  
Spot Location (QQQQ): NE - NE - NE - SW  
2460 Feet from  North /  South Section Line  
2790 Feet from  East /  West Section Line  
Sec. 27 Twp. 28 S. R. 32  East  West  
County: Haskell  
Date Well Completed: ~~11-19-2003~~ 11-21-1966  
Plugging Commenced: 01-14-2004  
Plugging Completed: 01-15-2004

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records |                             | Casing Record (Surface Conductor & Production) |              |                   |              |            |
|---------------------------|-----------------------------|--|--------------|-------------------|--------------|------------|
| Formation                 | Content                     | From   | To           | Size              | Put In       | Pulled Out |
| <u>Glorietta</u>          | <u>Prod</u><br><u>Water</u> | <u>1412'</u>                                   | <u>1422'</u> | <u>2 3/8" Tbg</u> | <u>1490'</u> | <u>-0-</u> |
|                           |                             |  |              |                   |              |            |
|                           |                             |  |              |                   |              |            |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

MIRU Acid Services. Pump 35 sacks Class "H" Cement with 50# hulls in first 10 sack. Pump at 350 psi. Cement at top of 2 3/8" tubing. Wait 10 minutes. Cement fell 2'. Tie back on to tubing and pump cement to top. Wait 10 minutes and cement still at top.  
Rig Down Acid Services. Cut 2 3/8" tubing 4' below ground level. Weld on ID Plate.

Plugging witnessed and approved by Mr. Kevin Strube with KCC.


Name of Plugging Contractor: XTO Energy Inc. (Company Tools) Acid Services LLC License #: 32864 32453  
Address: 210 Park Ave., Suite 2350 Oklahoma City, Oklahoma 73102  
Name of Party Responsible for Plugging Fees: XTO Energy Inc.  
State of Oklahoma County, Oklahoma, ss.

Bruce E. Hankins (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Bruce E Hankins  
(Address) 210 Park Ave., Suite 2350 Oklahoma City, Oklahoma 73102

SUBSCRIBED and SWORN TO before me this 21st day of January, 20 04

Joyce A. Williams My Commission Expires: 8-11-2004  
Notary Public



JOYCE A. WILLIAMS  
Oklahoma County  
Notary Public in and for Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202