

STATE OF KANSAS
CORPORATION COMMISSION
S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-21,189 100-00

LEASE NAME Turner "C"

WELL NUMBER 1

4290 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 18 TWP. 21S RGE. 15W (E) or (W)

COUNTY Pawnee

Date Well Completed 3-11-1985

Plugging Commenced 1-5-04

Plugging Completed 1-8-04

RECEIVED

JAN 30 2004

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR TURNCO DRILLING, INC.

ADDRESS P.O. Box 460 Great Bend, Kansas 67530

PHONE (620) 792-2441 OPERATORS LICENSE NO. 30517

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

A plugging proposal was approved on 8-1-03 (date)

Richard Lacey (KCC District Agent's Name).

ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 3875'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Sand</u>			<u>960</u>	<u>8-5/8"</u>	<u>960'</u>	<u>None</u>
<u>Pos.</u>			<u>3874</u>	<u>4-1/2"</u>	<u>3874'</u>	<u>2140'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each side. Plugged off bottom with sand to 3660' and 4 sacks cement. Cut casing loose @2140', pulled up to 1000', pumped 10 sacks gel, 100% hulls and 50 sacks cement. Pulled pipe up to 400', pumped, pumped 50 sacks cement, pulled rest of pipe and topped off with 20 sacks 60/40 pos. Plugging Complete. 6% gel

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Turnco Drilling, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 29th day of January, 20 04

[Signature]
Notary Public

My Commission Expires:



Form CP
Revised 05-