

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-30113-00-02
Spot: NENW Sec/Twnshp/Rge: 35-27S-7W
4620 feet from S Section Line, 3300 feet from E Section Line
Lease/Unit Name: MEADE Well Number: 1
County: KINGMAN Total Vertical Depth: 4279 feet

Operator License No.: 31337
Op Name: WILDCAT OIL & GAS LLC
Address: 10286 SW 170TH AVE
NASHVILLE, KS 67112

Production Casing Size: 4.5 feet: 3686 75 SX CMT
Surface Casing Size: 8.625 feet: 269 225 SX CMT

4139⁰⁷

Well Type: EOR UIC Docket No: E24434.1 Date/Time to Plug: 01/19/2004 10:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: JOE MACE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Sand to 3500' and 4 sacks of cement; 1150' and 35 sacks of cement; 650' and 35 sacks of cement; 320' - 0'.

RECEIVED
KCC DISTRICT #2

JAN 23 2004

Plugging Proposal Received By: JACK LUTHI

WitnessType: NONE

WICHITA, KS

Date/Time Plugging Completed: 01/19/2004 3:00 PM

KCC Agent: JACK LUTHI

Actual Plugging Report:

Sanded bottom to 3509 and 4 sacks of common cement. Shot 4-1/2" casing off at 2610'. Pulled 1150' and pumped 35 sacks of cement. Pulled to 650' and pumped 35 sacks of cement. Pulled to 320' and circulated cement to surface.

60/40 poz mix with 4% gel.

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 02 2004

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED TICKET #14643

Plugged through: CSG

District: 02

Signed

Jack Luthi

(TECHNICIAN)

INVOICED

DATE 2-2-04

INV. NO. 2004061138