

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22471-00-01
Spot: NENENW Sec/Twnshp/Rge: 10-7S-20W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: PROBASCO Well #: 7-1
County: ROOKS Total Vertical Depth: 3664 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 105 S BROADWAY, STE 1040
WICHITA, KS 67202

PROD Size: 4.5 feet: 3663 W/200 SXS CMT
SURF Size: 8.625 feet: 369 W/220 SXS CMT

#11908

Well Type: EOR UIC Docket No: E25885.1 Date/Time to Plug: 01/30/2004 8:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: HAROLD BELLRIEVE Company: VIKING RESOURCES, INC. Phone: (785) 635-4531

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Fluid level 2500'.
DV Tool at 1745' w/550 sxs cwc.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/30/2004 9:50 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 200 sxs 60/40 pozmix with 500# hulls.
Max. P.S.I. 1000#. S.I.P. 1000#.
Hooked up to backside instant pressure 500#.

Perfs:

Top	Bot	Thru	Comments
3534	3538		
3532	3556		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

RECEIVED

FEB 09 2004

KCC WICHITA

INVOICED

DATE

2-9-04

INV. NO.

2004061159

Form CP-2/3

FEB 06 2004

FRONTIER OIL COMPANY
1720 KSB&T BLDG.
WICHITA, KS 67202


#1 'A' PROBASCO

10-7-20W
NE NE NW

CONTR RED TIGER DRILLING CTY ROOKS

GEOLOGICAL RICHARD D. PARKER FIELD SLATE SW EXT
(1/4 W)

ELV 2164 KB SPD 9/7/84 CARD ISSUED 11/1/84 IP OIL WELL
2159 GL LKC 3534-3556 OA



SMP	Tops	Depth/Datum
ANH	1715+ 449
TOP	3142- 978
HEEB	3347-1183
TOR	3371-1207
LKC	3385-1221
BKC	3592-1428
CONG	3632-1468
RTD	3664-1500

API 15-163-22,471

8 5/8 " 369/220SX, 4 1/2 " 3663/200SX, FO TOOL AT 1745
DST (1) 3378-3412 (TOR, LKC) / 60-30-60-30, (1ST OP) WB,
(2ND OP) WB, REC 80' MSW, W/ FEW SPKS OIL, SIP 959-970#,
FP 48-85 / 70-74#
DST (2) 3410-72 (LKC) / 30-30-30-30, REC 20' M, W/ FEW SPKS
OIL, SIP 1217-1206#, FP 68-79 / 79-79#
DST (3) 3529-65 (LKC) / 60-30-60-30, (1ST OP) WB & DIED/
10", FLUSHED TOOL, VWB THRU-OUT, REC 30' OIL, 35' OCM,
SIP 113-272#, FP 45-56 / 68-79#
MICT - CO, PF (LKC) 3534-38, W/ 4 SPF, AC 500G (15% REG),
SWB DWN, SO, PF (LKC) 3552-56, W/ 4 SPF, AC 500G (15%
REG), SWB DWN, GSO, POP 9/28/84

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS