

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22117-00-01
Spot: E2NE Sec/Twnshp/Rge: 13-14S-19W
4620 feet from S Section Line, 660 feet from E Section Line
Lease Name: EARL SUNLEY OWWO Well #: 1
County: ELLIS Total Vertical Depth: 3790 feet

Operator License No.: 31240
Op Name: ENTERPRISE INC
Address: 2708 BARCLAY DR.
HAYS, KS 67601

PROD Size: 4.5 feet: 3789
SURF Size: 8.625 feet: 222 w/150 sxs cmt

#123¹⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/14/2004 12:00 PM
Plug Co. License No.: 33159 Plug Co. Name: GEIST, RON DBA WILDCAT WELL SERVICE
Proposal Rcvd. from: STEVE WEILERT Company: ENTERPRISE, INC. Phone: (785) 625-9699

Proposed Plugging Method: Ordered 300 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/14/2004 3:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Ran tubing to 1900' - spotted 150 sxs cement with 300# hulls.
Pulled tubing to 950' - circulated with 50 sxs cement and 200# hulls.
Pulled all tubing - squeezed 4 1/2" casing with 25 sxs cement.
Max. P.S.I. 700#. S.I.P. 700#.
Tied to 8 5/8" x 4 1/2" annulus - pressured to 500# immediately - took no cement.
Total of 275 sxs 60/40 pozmix - 10% gel and 500# hulls.

Perfs:

RECEIVED
FEB 09 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY, WERTH TANK-WATER.

Plugged through: TBG

District: 04

Signed Roger A Moses
(TECHNICIAN)

INVOICED

DATE 2-9-04
INV. NO. 2004061151

Form CP-2/3

JAN 28 2004

COLUMBIA PETROLEUM
 PARKADE PLAZA
 COLUMBIA, MO 65201

#1 EARL SUNLEY "OWWO"


13-14-19W
 C E/2 NE

CONTR UNKNOWN

CTY ELLIS

GEOLOGICAL

FIELD EXPERIMENT SW



ELV 2154 KB SPD 6/2/81

CARD ISSUED 10/13/83

IP P 10 BO & 10 BWPD

API 15-051-22,117-A

LKC 3494-3499 &
 3621-3625

SMP	Tops	Depth/Datum
	TOP	3138-984
	HEEB	3406-1252
	TOR	3425-1271
	LANS	3454-1300
	BKC	3683-1529
	MARM	3709-1555
	PENN-CONG	3732-1578
	RTD	3790-1636
	NO LOG	

OLD INFO: OPERATOR WAS L & F OIL OPERATIONS, #1 EARL SUNLEY, SPD 10/14/80, SET 8 5/8" 222/150 SX, COMP. AS D & A / PENN-CONG, (CARD ISSUED 8/27/81), CONTR: LAWBANCO DRILLING, INC., GEOL: CLIFF OTTAWAY
 NO DST'S
 NEW INFO: FR 10/10/83, RE-ENTERED 6/2/81, WSH DWN TO OTD, SET 4 1/2" 3789, PF (CONG) 3740-42, AC 2750 G (15%), MGT - CO, SION, HFV, SET BP AT 3660, PF (LKC J) 3621-25, AC 250 G (MA), SWB DWN, SO, RE-AC 1500 G (28%), SWB DWN, GSO, PF (LKC D) 3494-99 & (LKC C) 3478-83, AC 500 G (15% MA), HAD COMMUNICATION, SQZ'D (C,D) PFS W/125 SX, RE-PF (LKC D) 3494-99, AC 250 G (15% MA), SWB DWN, GSO, POP, P 10-12 BO & 10 BWPD

COPYRIGHT 1983
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

WAGICEY