

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21528-00-00
Spot: S2SW Sec/Twnshp/Rge: 12-21S-7W
330 feet from S Section Line, 3960 feet from E Section Line
Lease Name: M PALLISTER Well #: 3-12
County: RICE Total Vertical Depth: 3450 feet

Operator License No.: 5610
Op Name: BRUCE OIL COMPANY L.L.C.
Address: 1704 LIMESTONE RD.
MCPHERSON, KS 67460

PROD Size: 5.5 feet: 3400 75 SX CMT
SURF Size: 8.625 feet: 205 200 SX CMT
\$112.13

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/27/2004 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MACE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Sand to 3300' & 5 sacks of cement; Shot 5-1/2" @ 2430'; 35 sacks of cement @ 1050'; 35 sacks of cement @ 600'; 255' to 0'.
RECEIVED
KCC DISTRICT #2
FEB 2 2004

Plugging Proposal Received By: JACK LUTHI Witness Type: PARTIAL WICHITA, KS
Date/Time Plugging Completed: 01/27/2004 7:30 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Sanded bottom to 3300' and 5 sacks of common. Cut 5-1/2" casing off at 2430'. Pulled to 1050' and pumped 35 sacks of cement. Pulled to 600' and pumped 35 sacks of cement. Pulled to 255' and circulated cement to surface.

60/40 poz mix with 4% gel.

Perfs: RECEIVED
KANSAS CORPORATION COMMISSION
FEB 02 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED TICKET #14980

Plugged through: CSG

District: 02

Signed Jack Luthi
(TECHNICIAN)
INVOICED
DATE 2-3-04
2004061140