

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-017-20093-00-00
Spot: SENWNENE Sec/Twnshp/Rge: 11-20S-7E
660 feet from N Section Line, 660 feet from E Section Line
Lease/Unit Name: HYNSON Well Number: 1-11
County: CHASE Total Vertical Depth: 1450 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 1450 150 SX CMT
Surface Casing Size: 7 feet: 11 UNKNOWN

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/26/2003 8:00 AM
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL DBA MCPHERSON DRILLING CO.
Proposal Rcvd. from: LAWRENCE JACKSON Company: AMERICAN ENERGIES CORP. Phone: (620) 793-2146

Proposed
Plugging
Method:

CEMENT PLUG @ PERFORATION, FILL WITH MUD. 20 SX AT TOP OF 4 1/2" CASING.

RECEIVED
KCC DISTRICT #2

JAN 23 2004

WICHITA, KS

Plugging Proposal Received By: MICHAEL WILSON
Date/Time Plugging Completed: 12/26/2003 5:00 PM

Witness Type: PARTIAL
KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Ran tubing to 1,354' and spotted 28 sxs. cement. Pulled tubing to 272' and circulated 215 sxs. cement to the surface. Ran tubing to 15' on outside of 4 1/2" casing and circulated 5 sxs. cement to the surface.

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 05 2004

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY UNITED CEMENTING & ACID CO., INC. INVOICE #5071

Plugged through: TBG

District: 02

Signed

Michael Wilson

(TECHNICIAN)

INVOICED
2-5-04
2004061147