

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20431-00-00
Spot: NESWSE Sec/Twnshp/Rge: 5-24S-17W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: CARPENTER Well #: 1
County: EDWARDS Total Vertical Depth: 4490 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

PROD Size: 4.5 feet: 4488 WITH 150 SX CMT
SURF Size: 8.625 feet: 261 WITH 225 SX CMT

93
#145

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/29/2004 3:00 PM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND BACK TO 4290' WITH 4 SX CMT. PLUG AT 1250' WITH 50 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 275' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT. USE 15 SX GEL FOR SPACER.

Plugging Proposal Received By: KEVIN STRUBE

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 01/30/2004 1:30 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4458'. 1171-1191 ANHYDRITE. SANDED TO 4280' & 4 SX CMT ON TOP OF SAND WITH BAILER. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 1250' WITH 15 SX GEL - 50 SX CMT. NO CIRCULATION. 2ND PLUG AT 600' WITH 50 SX GEL - 800# HULLS - 50 SX CMT. 3RD PLUG AT 290' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.


Perfs:

Top	Bot	Thru	Comments
4359	4362		
4343	4344		

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2250' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey
(TECHNICIAN)

RECEIVED
FEB 04 2004
KCC WICHITA

INVOICED
DATE 2-4-04
BILL NO. 2004061145
2004061145