

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-00682-00-00
Spot: S2S2SE Sec/Twnshp/Rge: 36-3S-24W
330 feet from S Section Line, 1320 feet from E Section Line
Lease Name: LAWSON Well #: 4
County: NORTON Total Vertical Depth: 3800 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: PO BOX 2757 202 SOUTH ST. FRANCIS
WICHITA, KS 67201

PROD Size: 5.5 feet: 3797 100 SX CMT
SURF Size: 8.625 feet: 267 135 SX CMT #123⁵⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/13/2004 8:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (308) 345-1598

Proposed Plugging Method: Ordered out 235 sxs Swift Multi-Density Cement with 500# hulls.
Fluid level 545'. Tubing stuck.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/13/2004 11:45 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

M.I.R.U. Perf Tech ran free point and backed tubing off at 2532'.
Pulled one joint - 5 1/2" casing nipple broke off. Shut down unit.
01-13-2004 - Swift Services pumped 135 sxs with 500# hulls down tubing - cement circulated.
PTOH. Squeezed with 40 sxs.
Max. P.S.I. 800#. S.I.P. 500#.
Hooked up to backside and pumped 45 sxs.
Max. P.S.I. 100#. Shut in one hour - topped off with 50 sxs - 0#.

Perfs:

Top	Bot
0	

RECEIVED
FEB 09 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED
DATE 2.9.04
INV. NO. 2004061153

Form CP-2/3

JAN 27 2004

HARRY GORE

#1 LAWSON

36-3-21W
S2 S2 SE

Contr. EMPIRE DRILLING

NORTON County

E 2168 RB Comm.

Comp. 2-26-54

IP 162 BOPD

PERM PMP

Tops	Depth	Datum
HEEB	3198	-1030
KC	3538	-1070
ARB	3794	-1326
TD	3802	-1334

Casing
5" 3797

DD 3802: 1000' FU: PMP
10 BOPD

NORTON POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

INVOICE