

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-00681-00-00
Spot: NENESE Sec/Twnshp/Rge: 36-3S-24W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: LAWSON Well #: 3
County: NORTON Total Vertical Depth: 3768 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: PO BOX 2757 202 SOUTH ST. FRANCIS
WICHITA, KS 67201

PROD Size: 5.5 feet: 3765 100 SX CMT
SURF Size: 8.625 feet: 257 150 SX CMT

\$ 122⁴⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/14/2004 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (308) 345-1598

Proposed Plugging Method: Ordered out 235 sxs Swift Multi-Density Cement with 500# hulls.
Fluid level 2800'. Prod.Perfs 3763' - 3768' - O.H.
Squeezed 1580' w/250 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/14/2004 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Swift Services pumped 180 sxs SMD with 500# hulls - 0#. Shut in one hour. Topped off with 20 sxs.
Hooked up to backside and pumped 45 sxs down 8 5/8".
Max. P.S.I. 200#. S.I.P. 150#.

Perfs:	
Top	Bot
0	

RECEIVED
FEB 09 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

FD -

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

2-9-04

INV. NO.

2004061153

JAN 27 2004

HARRY GORE #3 LAWSON 36-3-21W
NE-NE SE

Contr. EMPIRE DRUG NORTON County


E. 21/11 Reomm. Comp. 9-25-53 IP 348 BOPD
PHY POT

Tops	Depth	Datum
ANH	2025	116
TOP	3323	-882
HEFB	3473	-1032
TOR	3500	-1059
LANS	3515	-1074
B/KC	3696	-1255
ARB	3763	-1322
TD	3768	-1327

Casing
8" 257
5" 3764

DP 3768: ACID 500:
10 BOPH

NORTON POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

NORTON POOL