

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-00697-00-00
Spot: S2S2NE Sec/Twnshp/Rge: 30-3S-23W
3300 feet from S Section Line, 1320 feet from E Section Line
Lease Name: HORNING Well #: 2
County: NORTON Total Vertical Depth: 3772 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: PO BOX 2757 202 SOUTH ST. FRANCIS
WICHITA, KS 67201

PROD Size: 5.5 feet: 3766 100 SX CMT
SURF Size: 8.625 feet: 210 150 SX CMT

3/122 59

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/12/2004 8:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (308) 345-1598

Proposed Plugging Method: Ordered out 235 sxs Swift Multi-Density Cement with 500# hulls.
Prod. Perfs 3764' - 3769'. Fluid level 550'. Tubing stuck.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/12/2004 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

M.I.R.U. Perf Tech ran free point - found tubing stuck at 2150'. Backed tubing off at 2130'.
Pulled one joint. Swift Services pumped 100 sxs with 500# hulls. - cement circulated.
PTOH. Squeezed with 55 sxs. Hole full.
Hooked up to backside and pumped 80 sxs.
Max. P.S.I. 200#. S.I.P. 0#. Hole full.

Perfs:	
Top	Bot
0	

RECEIVED
FEB 09 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

M.D. Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 2-9-04
INV. NO. 2004061153

JAN 27 2004

IMAGINATION

HARRY GORE

#2

HORNING

30-3-23W
S2 S2 NE

Contr. EMPIRE DRILLING

NORTON County

E 2446RB

Comm.

Comp.

10-8-54

IP

139 BOPD

PERM PMPG

Tops	Depth	Datum
ANH	2043	403
HEEB	3489	-1043
TOR	3515	-1069
LANS	3531	-1085
ARB	3765	-1319
TD	3772	-1326

Casing
8" 210
5" 3766

175' O.I.H.: DD 3772: PMP
140 BO/18 HRS:

NORTON POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS