

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-00706-00-00
Spot: SESESW Sec/Twnshp/Rge: 35-3S-24W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: HENRY Well #: 2
County: NORTON Total Vertical Depth: 3723 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: PO BOX 352 370 W WICHITA AVE
RUSSELL, KS 67665

PROD Size: 5.5 feet: 3721 100 SX CMT
SURF Size: 8.625 feet: 297 150 SX CMT

121⁰⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/13/2004 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GARY REH Company: JOHN O. FARMER, INC. Phone: (785) 483-3144

Proposed Plugging Method: Ordered out 235 sxs Swift Multi-Density Cement with 500# hulls.
Fluid level 400'. Perfs 3719' - 3723'.
Squeezed 1600' w/175 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/13/2004 4:50 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

M.I.R.U. Ran tubing to 2100'.
Swift Services pumped 100 sxs SMD with 500# hulls - cement circulated.
PTOH. Squeezed with 65 sxs.
Max. P.S.I. 600#. S.I.P. 300#.
01-14-2004 - Topped 5 1/2" off with 10 sxs. - hole full.
Hooked up to backside and pumped 50 sxs SMD.
Max. P.S.I. 200#. S.I.P. 150#.

Perfs:	
Top	Bot
0	

RECEIVED
FEB 09 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 2-9-04
NO. 200406153

JAN 27 2004

WMAOIGSP

HARRY GORE

#2

HENRY

35-3-24W
SE SE SW

Contr. EMPIRE DRILLING NORTON County


E. 2400RB Comm. 10-8-54 Comp. IP 193 BOPD, NO WTR

Tops	Depth	Datum
HEEB	3420	-1020
TOR	3446	-1046
LANS	3460	-1060
B/KC	3646	-1246
ARB	3719	-1319
TD	3723	-1323

Casing
8" 297
5" 3721

CO 3723

NORTON POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

15-137-00706-00-00

Barb:

**John O. Farmer, Inc. purchased this lease
from Gore Oil Company with the
conditions that Gore Oil Company plug
this well.**

Please bill the following:

**Gore Oil Company #5552
P.O. Box 2757
Wichita, Kansas 67201**

**Thanks
Sheila
District #4
Hays, Kansas 67601**