

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00294-00-00
Spot: SWSESE Sec/Twnshp/Rge: 34-11S-16W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: CHRISLER B Well #: 1
County: ELLIS Total Vertical Depth: 3423 feet

Operator License No.: 31385
Op Name: M G OIL INC
Address: PO BOX 162
RUSSELL, KS 67665

PROD Size: 5.5 feet: 3422
SURF Size: 8.625 feet: 996

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/21/2004 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TERRY PIESKER Company: M G OIL, INC. Phone: (785) 483-4357

Proposed Plugging Method: Ordered out 485 sxs 60/40 pozmix - 10% gel - 500# hulls.
Emergency plug with rig over the hole.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/21/2004 2:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 2700' - mixed and pumped 100 sxs cement with 500# hulls.
Pulled up to 1000' - spotted 125 sxs cement.
POOH. Swaged onto 5 1/2" - pumped 125 sxs cement.
Max. P.S.I. 100#. S.I.P. 50#.
Hooked up to the 8 5/8" - pumped 135 sxs cement.
Max. P.S.I. 100#. S.I.P. 50#.

Perfs:	
Top	Bot
0	

RECEIVED
FEB 09 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

10

Signed Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE

29-04

REF. NO.

2004061156

JAN 27 2004

RUPP-FERGUSON OIL COMPANY

#1 CHRISLER 'B'

34-11-16W

SW SE SE

Contr. RUPP-FERGUSON

ELLIS County

E 1825RB Comm. Comp. 6-12-59 IP

100 BOPD

PHY POT

Tops	Depth	Datum
ANH	991	+834
HEEB	2991	-1166
TOR	3014	-1189
LANS	3038	-1213
ARB	3373	-1548
TD	3423	-1598

Casing
 8" 996
 5" 3422
 DST 3069-3120/1 HR, 30' G, 30'
 OCM, 128' W, BHP 920#
 DST 3130-3220/1 HR, 279' V. SL OC
 SW, BHP 1220#
 DST 3375-83/1 HR, 1643' GIP, 1220'
 O, BHP 1020#
 PERF 3374-84: 27 BO/6 HR: ACID.
 1000: REPERF: 14 BOPH/2 HR: TR W:
 97 BO/6 1/2 HR: SSW

+	+	+	+
+	+	+	+
+	+	+	+
+	+	+	+

BLUE HILL NW POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

DOWN THE ROAD

INDICED