

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03396-00-00
Spot: NESWNE Sec/Twnshp/Rge: 25-16S-12W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: RIEMANN Well #: 4
County: BARTON Total Vertical Depth: 3240 feet

Operator License No.: 6883
Op Name: ROBINOWITZ OIL COMPANY
Address: 7130 S. LEWIS, STE 910
TULSA, OK 74136

PROD Size: 7 feet: 3225 100 SX CMT
SURF Size: 10.75 feet: 761 **\$105³⁰**

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/13/2004 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 793-2299

Proposed Plugging Method: Perfed from Log Tech at 775' and 1475'.
Perfs 2872' - 2888'; 2898' - 2908'; 3065' - 3072'; 3170' - 3172'.
Casing leak at 860'. Casing parted at 1178'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/16/2004 5:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

RIH with tubing and stacked out at 1178' - pulled one joint to 1147' - pumped 265 sxs with 900# hulls mixed in.
Pulled to 800' - pumped an additional 50 sxs - no returns left - set overnight - total 315 sxs with 900# hulls.
Witnessed by Pat Staab

01-14-2004 - RIH with tubing to 1000' - pumped 100 sxs 60/40 pozmix - 3% cc and 600# hulls - no returns - well on vacuum.
Pulled tubing to 620' - pumped 112 sxs gel and 2300# hulls, followed with 50 sxs 60/40 pozmix - 3% cc - 10% gel with 200# hulls.
Total 150 sxs 60/40 pozmix -10% gel - 5 bags cc and 3100# hulls. Witnessed by Pat Staab.

01-15-2004 - Put pickup bed full of 1" - 1 1/2" chat down well. Tagged at 750'. Approximately 30' at fluid.
Pumped 200 sxs ASC cement - 1% cc with 5 lbs coal seal per sack. Blow on backside - static out at 400'.
Witnessed by Case Morris.

01-16-2004 - Tied onto backside and circulated cement up inside with 240 sxs cement with 600# hulls.
Hole stayed full. Witnessed by Case Morris.

Perfs:	
Top	Bot
775	1475

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Case Morris

(TECHNICIAN)

RECEIVED
FEB 09 2004
KCC WICHITA

INVOICED
2-9-04
2004061158

JAN 22 2004

1
 MAOICEN

BLACK MARSHALL OIL CO

#4 J. R. RIEMANN

25-16-12W
NE SW NE

Contr. _____ BARTON _____ County

E. 1942 Comm. 8-13-44 Comp. 9-19-44 IP 31A BOPD

Tops	Depth	Datum
ANHY	762	
TOP	2680	
LANS	3068	
TD	3210	

Casing.
12" 445
7" 3225

*10 3/4 to 761'
CSJ Log to 860'*

A/2000
SO 2880-85
SSO 2892-97
2 BOPH 3063-69.

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS