

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-03400-00-00  
Spot: NENWNE Sec/Twnshp/Rge: 25-16S-12W  
4950 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: REIMANN Well #: 8  
County: BARTON Total Vertical Depth: 3338 feet

Operator License No.: 6883  
Op Name: ROBINOWITZ OIL COMPANY  
Address: 7130 S. LEWIS, STE 910  
TULSA, OK 74136

PROD Size: 5.5 feet: 3328 50 SX CMT  
SURF Size: 10.75 feet: 770

*8/108 49*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/16/2004 11:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (316) 938-2943

Proposed Log Tech perfd 775' and 1475' - 2 shot perf.  
Plugging Perfs 3242' - 3248'; 3276' - 3288'.  
Method: Casing good. Dakota 171' - 421'. Anhy 760' - 780'. Salt 1200' - 1437'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/17/2004 3:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

01-16-2004 - Ran tubing to 1500'.  
Pumped 400 sxs 60/40 pozmix - 10% gel cement with 600# hulls.  
Had fluid circulating out but no cement. Let set overnight.  
  
01-17-2004 - Tagged cement at 600'.  
Tried to pump down backside - locked up at 400#.  
Perforated at 350'.  
Pumped 120 sxs cement down casing. Cement circulated up backside.

Perfs:	
Top	Bot
775	1475

RECEIVED  
FEB 09 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed *Case Morris*

INVOICED (TECHNICIAN)

DATE 2-9-04  
INV. NO. 2004061158

Form CP-2/3

JAN 28 2004

Black-Marshall Oil Co.

# 8

Reimann

25-16-12W  
NE NW NE

Contr. ....

Barton County

E- 1921

Comm. 4-6-47

Comp. 6-13-47

IP 351 BO/D

Tops	Depth	Datum
ANHY	760	
TOP	2670	
LANS	3165	
GORN	3327	
T. D.	3338	

Casing  
~~12" 475~~ pulled 1 Bailer OFH, 3238-45  
 10" 770 At 3328, 160' OIH  
~~8" 2132~~ pulled 2D 3338  
~~7" 3190~~ pulled 1600' OIH-45 Min  
 5" 3328 SWB 80 BO/6 Hrs.

80 3164-67.  
 80 3246


INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

12/26/47  
 W.M.  
 W.M.  
 W.M.