

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22955-00-00
Spot: E2NW Sec/Twnshp/Rge: 22-8S-23W
1380 feet from N Section Line, 2080 feet from W Section Line
Lease Name: MARTHA Well #: 1
County: GRAHAM Total Vertical Depth: 3725 feet

Operator License No.: 32016
Op Name: WELLS. RODGER D. DBA PIONEER RES
Address: 177 W. LINSTONE RD.
PHILLIPSBURG, KS 67661

SURF Size: 8.625 feet: 218 w/175 sxs cmt

\$121⁰⁶

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/27/2004 2:30 AM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC
Proposal Rcvd. from: BURT BEERY Company: SHIELDS OIL PRODUCERS INC Phone: (785) 735-4637

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele persack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB WitnessType: NONE
Date/Time Plugging Completed: 01/27/2004 3:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 1878' w/25 sxs.
2nd. Plug at 1046' w/100 sxs.
3rd. Plug at 270' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

RECEIVED
FEB 09 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

INVOICED

2-9-04
2004061160

Form CP-2/3

JAN 28 2004