

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-22303-001 ²⁴⁵¹³

LEASE NAME MLP Smith A

WELL NUMBER 1

3960 Ft. from S. Section Line

1320 Ft. from E Section Line

SEC. 30 TWP. 31 RGE. 38 (S) or (W)

COUNTY Stevens 9-17-1999

Date Well Completed 2-4-92

Plugging Commenced 1-12-04

Plugging Completed 1-13-04

RECEIVED

FEB 04 2004

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N. Kansas PO Box 2528 Liberal, KS. 67905

PHONE (620) 629-4200 OPERATORS LICENSE NO. 5447

Character of Well oil

(Oil) Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-8-04 (date)

by Jim Holland (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Cherokee Depth to Top 4974' Bottom 4978 T.O. 6158'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Surf</u>			<u>1671</u>	<u>8 5/8</u>	<u>1671</u>	<u>-</u>
<u>Prod</u>			<u>6158</u>	<u>5 1/2</u>	<u>6158</u>	<u>1083</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each so

Mixed 300 lb. hulls to 25 sx cmt. to plug perfs from 4974 to 4774. Shot 5 1/2 loose.
Circ. hole w/mud to mixed 30 sx 1083 to 983 30 sx 600 to 500
10 sx 40 to 0 Cut off & capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.

STATE OF Kansas COUNTY OF Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact
statements, and matters herein contained and the log of the above-described well as filed with
the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS. 67905

SUBSCRIBED AND SWORN TO before me this 29th day of Jan, 2004



ANITA PETERSON
MY COMMISSION EXPIRES
October 1, 2005

Expires: Oct. 1, 2005

Anita Peterson
Notary Public