

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-081-20674-00-01
API NUMBER ~~15-081-20674-00-01~~

RECEIVED

FEB 06 2004

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Dewell

WELL NUMBER 1-19A

1120 Ft. from S Section Line

1070 Ft. from E Section Line

SEC. 19 TWP. 29 RGE. 32 (E or W)

COUNTY Haskell

Date Well Completed 2-19-94

Plugging Commenced 11-25-03

Plugging Completed 11-26-03

KCC WICHITA

LEASE OPERATOR C+R Petroleum Co.

ADDRESS PO Box 404 Spearman TX 79081

PHONE (806) 659 3309 OPERATORS LICENSE NO. 31666

Character of Well oil gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-24-03 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? _____

Producing Formation Chester/Atoka Depth to Top 5088' Bottom 5377' T.D. 5760'
5608'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Chester (oil) SWD</u>	<u>Oil & Gas</u>	<u>5364</u>	<u>5377</u>	<u>8 5/8</u>	<u>1851</u>	<u>-</u>
<u>Atoka</u>	<u>Oil & Gas</u>	<u>5088</u>	<u>5142</u>			
<u>4 1/2</u>			<u>5646</u>	<u>4 1/2</u>	<u>5646</u>	<u>1189</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Mixed 400 lb hulls & 20 sx cmt to plug perfs from 5088 to 4888, pumped mud spacer to 1850, then 20 sx cmt from 1850 to 1650, mud to 0. Shoot & pull 4 1/2 to 650. Circ hole w/mud 50 sx 650 to 500 10 sx 40 to 0 Cut off & capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: C+R Petroleum Co.


STATE OF Texas COUNTY OF Hansford, ss.

Curtis F Covington, owner of C+R Petroleum (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed th the same are true and correct, so help me God.

(Signature) Curtis F Covington

(Address) P.O. Box 404, Spearman, TX 79081

SUBSCRIBED AND SWORN TO before me this 4th day of February, 2004



Jennifer Lozano
Notary Public

Expires: May 29, 2005