

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-067-21215-00-01

LEASE NAME MLP Quiett A

WELL NUMBER 1

3450 Ft. from S. Section Line

4620 Ft. from E Section Line

SEC. 25 TWP. 30 RGE. 35 (W)

COUNTY Grant

Date Well Completed 8-21-93

Plugging Commenced 1-16-04

Plugging Completed 1-16-04

RECEIVED

FEB 04 2004

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N. Kansas PO Box 2528 Liberal, KS 67905

PHONES (620) 629-4200 OPERATORS LICENSE NO. 5447

Character of Well oil

(Oil) Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-14-04 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 5216' Bottom 5229 T.D. 5750'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Sand</u>			<u>1635</u>	<u>8 5/8</u>	<u>1635</u>	<u>-</u>
<u>Cond</u>			<u>70</u>	<u>20</u>	<u>70</u>	<u>-</u>
<u>Prod</u>			<u>5749</u>	<u>5 1/2</u>	<u>5749</u>	<u>-</u>
<u>M.S.C.C.</u>			<u>294</u>			
<u>CIBP</u>			<u>5460</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each so Mixed 300 lb. hulls + 25 sx cmt. to plug perms from 5216 to 5016, pumped mud spacer to 1700, 25 sx cmt. 1700 to 1500, mud spacer to 500, then 60 sx 500 to 0. Mixed 6 sx down annulus from 36 to 0. Cut off 8 5/8 + 5 1/2 + capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.

STATE OF Kansas COUNTY OF Seward, ss.


Kenny Andrews (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed th the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 30th day of Jan, 2004

Anita Peterson
Notary Public



My Commission Expires: Oct. 1, 2005