

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-067-2121600-00

LEASE NAME MLP Scott A

WELL NUMBER 4

660 Ft. from S. Section Line

3200 Ft. from E Section Line

SEC. 23 TWP. 30 RGE. 35 (E or W)

COUNTY Grant

Date Well Completed 6-15-93

Plugging Commenced 1-14-04

Plugging Completed 1-14-04

RECEIVED

FEB 04 2004

KCC WICHITA

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N. Kansas Rd Box 2528 Liberal, KS 67905

PHONE(S) (620) 629-4200 OPERATORS LICENSE NO. 5447

Character of Well oil

(Oil) Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-13-04 (date)

by Steve Middleton (KCC District Agent's Name).

is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Chester Depth to Top 5440 Bottom 5458 T.O. 5750'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-------------|---------|----------|-------------|--------------|-------------|------------|
| <u>Surf</u> | | | <u>1644</u> | <u>8 5/8</u> | <u>1644</u> | <u>-</u> |
| <u>Prod</u> | | <u>5</u> | <u>5749</u> | <u>5 1/2</u> | <u>5749</u> | <u>-</u> |
| <u>Cond</u> | | | <u>71</u> | <u>20</u> | <u>71</u> | <u>0</u> |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each so Mixed 300 lb. hulls + 25 sx cmt. to plug perfs from 5440 to 5240, mud spacer to 1700, mixed 25 sx from 1700 to 1500, mud spacer to 500, mixed 60 sx cmt 500 to 0. Pumped 10 sx cmt down annulus from 60 to 0. Cut off 8 5/8 & 5 1/2 & capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.


STATE OF Kansas COUNTY OF Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) Po Box 2528 Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 29th day of Jan, 19 2004



Anita Peterson
Notary Public

My Commission Expires: Oct. 1, 2005