

STATE OF KANSAS
OIL & GAS COMMISSION
S. Market, Room 2078
Tulsa, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-03396-00 00
Comp. 2-5-44

RECEIVED
FEB 03 2004
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Riemann
WELL NUMBER 4
3630 Ft. from S Section Line
1650 Ft. from E Section Line
SEC. 25 TWP. 16 RGE. 12W (E) or (W)
COUNTY Barton
Date Well Completed _____
Plugging Commenced 1-13-04
Plugging Completed 1-16-04

LEASE OPERATOR ROBINOWITZ OIL COMPANY
ADDRESS 7130 D. Lewis, Suite 910, Tulsa, OK. 74136

PHONE (918) 481-7130 OPERATOR'S LICENSE NO. 6883

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

A plugging proposal was approved on _____ (date)
_____ Case Morris (KCC District Agent's Name).

ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3317'
3240

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>surf</u>			<u>761</u>	<u>10" 750</u>	<u>761'</u>	<u>None</u>
			<u>3225</u>	<u>7"</u>	<u>3225'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each sack.
Perforated well @1475' & 775'. Ran 2-3/8" tubing to 1147', pumped 265 sacks 60/40 pos, 900# hulls, pulled tubing to 800' & pumped 50 sacks cement. Let set overnight. Ran tubing to 1000' & pumped 10 sacks 60/40 pos, 3%CC & 600# hulls, pulled tubing to 620', pumped 112 sacks gel & 2300# hulls & 60 sacks 60/40 pos, 3%cc, pulled tubing, ran chat down 7" casing & tagged @750'. 30' fluid over chat, pumped 200 sxs. ASC Cement, 1%cc w/5 lbs. coal seal per sx. Tied onto backside & circulated up inside w/240 sxs. cement w/600# hulls. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529
Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: _____

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 2nd. day of February, 20 04

[Signature]
Notary Public

My Commission Expires: _____

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-05

Form CP
Revised 05-