

STATE OF KANSAS  
CORPORATION COMMISSION  
S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-009-03395-00-00  
Comp. 2-5-44

**RECEIVED**  
**FEB 03 2004**  
**KCC WICHITA**

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE NAME Riemann

WELL NUMBER 3

4020 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 25 TWP. 16 RGE. 12W (E) or (W)

COUNTY Barton

Date Well Completed 3/22/44

Plugging Commenced 1-15-04

Plugging Completed 1-15-04

LEASE OPERATOR ROBINOWITZ OIL COMPANY

ADDRESS 7130 S. Lewis, Suite 910, Tulsa, OK. 74136

PHONE (918) 481-7130 OPERATOR'S LICENSE NO. 6883

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

A plugging proposal was approved on 10-21-2003 (date)

Case Morris (KCC District Agent's Name).

ACO-1 filed?                      If not, is well log attached?                     

Producing Formation                      Depth to Top                      Bottom                      T.D. 3326' 3330'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Sand</u>			<u>766</u>	<u>10" 750</u>	<u>766'</u>	<u>None</u>
<u>Prod</u>			<u>3320</u>	<u>5-1/2"</u>	<u>3320'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from        feet to        feet each side. Perforated well @775' and 1475'. Ran 2-3/8" tubing to 1500', pumped 140 sacks cement with 600# hulls, layed down tubing, pumped 160 sacks cement down 5-1/2" and 40 sacks cement down backside, 60/40 pos, 10% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Robinowitz Oil Company

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith are the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 2nd day of February, 2002

[Signature]  
Notary Public

My Commission Expires:                     

